

KADUR DIVISION:

Notification dated 16th March 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 10th April 1933, at 3 P.M., for "Constructing a new Middle School Building at Lakkavalli, Tarikere Taluk." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office, Chikmagalur, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one hundred and sixty (Rs. 160) in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing a new Middle School Building at Lakkavalli, Tarikere Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be quoted for each and every item.

10. Percentage quotations either below the lowest tender or below the estimated rates will not be accepted.

11. In all matters of dispute regarding quality of work or rates, the decision of the Superintending Engineer, Shimoga Circle, Shimoga, is final and legally binding.

12. No claims of enhanced rates should be preferred after the acceptance of tender or at any time during execution of work.

13. For Lumpsum items and also items found necessary during execution, rates as per current schedule rates or at tendered rates for such of the items as form a portion in Lumpsum provision, or as per date of worked out and approved by the Superintending Engineer, Shimoga Circle, will be allowed.

14. No representations regarding rates, etc., for the rejected tenderers will be considered.

15. The contractor shall hold himself responsible for good behaviour of his employees of all grades.

L. A. H. WINCKLER,
Executive Engineer.

DAM CONSTRUCTION AND No. I, IRWIN CANAL DIVISION,
KRISHNARAJASAGARA.

Notification.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Dam Construction and No. I, Canal Division, Krishnarajasagara, up to 4 P.M. of 3rd April 1933, for the work of constructing a combined building for Kannada and Urdu Primary Boys' School at Yedatore New Town. An approximate estimate of the quantities is given below. These quantities are not guaranteed. The work should be completed by the middle of June 1933.

2. The plans detailed estimate and conditions may be seen at the Executive Engineer's Office at Krishnarajasagara between the hours of 11 A.M. and 5-30 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred only (Rs. 200) in cash or Government promissory notes as earnest money and be superscribed "Tender for constructing a combined building for Kannada and Urdu Primary Boys' School, at Yedatore New Town" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned on production of the receipt.

9. The monthly rate of progress should be specified in the tender.

Abstract Estimate of quantities for constructing a combined building for Kannada and Urdu Boys' Primary School at Yedatore New Town.

Sl. No.	Items of work	Unit	Quantity
1	Earth work excavation for foundation and filling in basement ...	C.yd.	90
2	Lime concrete for foundation	C.ft.	693
3	Size stone in clay for foundation and basement	"	3108
4	Burnt brick in clay superstructure	"	4088
5	Do in lime mortar	"	1008
6	Arch work	"	244
7	Burnt stone slabs with one line dressed	S.ft.	413
8	Supplying and fixing burnt stone pillars	No.	16
9	Teak wood wrought and put up with wood oiling... ..	C.ft.	196.68
10	Rolled steel joists	Cwt.	1.43
11	Teakwood doors battened with hinges, bolts, etc. complete ..	S.ft.	240
12	Do windows half glazed and half panelled, etc., complete.	"	264
13	Moulded Ventilators (perforated)	"	45
14	Teakwood Ventilators glazed	"	6.28
15	Roofing with 1st class Mangalore tiles on 2" x 1" teak-reeper ...	Sqr.	44.97
16	Ridge tiles set in mortar	R.ft.	165.25
17	Valley tiles set in mortar	"	66
18	Zinc sheets for valleys over teak wood planks	S.ft.	198
19	Teak wood plain cave boards 9" deep including painting ..	R.ft.	346.25
20	Chunam plastering	Sqr.	60
21	Stucco plastering	"	26.92
22	Chunam mortar painting	"	576
23	Whitewashing	"	60.00
24	Colourwashing to stucco plastering with cement wash ..	"	26.92
25	Supplying and fixing teak wood finials with painting ..	No.	4
26	Do do pendants do	"	14
27	Chunam borders over roof	R.ft.	1.54
28	Flooring with 1st class Mangalore tiles (square) on 3" concrete bed and cement pointing.	Sqr.	19.32
29	Flooring with Cadapah slabs over 3" concrete bed and cement pointing.	"	8.28
30	Chocolate painting two coats to doors and windows ..	"	11.34
31	Pucca terrace over vestibule	"	74
32	Constructing parapet wall over vestibule	R.ft.	24.25
33	Cornice to the vestibule portion	"	24.25
34	Clearing site and levelling ground	Lumpsum	
35	Constructing latrine	Lumpsum	
36	Ornamental features over arches, windows and ventilators ..	Lumpsum	
37	Water connection to the building	Lumpsum	

N. SARABHOJA,
Executive Engineer.